

Date: Tuesday, 4/17/2007 11:12:50 AM  
 User: Kim Johnston

## Process Sheet

Customer : CU-DAR001 Dart Helicopters Services Drawing Name : AFT TUBE ASSEMBLY  
 Job Number : 31859  
 Estimate Number : 10699  
 P.O. Number :  
 This Issue : 4/17/2007 S.O. No. :  
 Prsht Rev. : NC Part Number : D3391025  
 First Issue : 7-1 Type : LANDING GEAR Drawing Number : D3391 REV F  
 Drawing Revision : F  
 Previous Run : 31858 Material :  
 Due Date : 5/30/2007 Qty: 1 Um: Each  
 Written By :  
 Checked & Approved By : 4/17/07  
 Comment : Est Rev B 06-02-07 ECN773 dwg rev. D EC  
 Est Rev C 06-03-28 Update Manufacturing Instructions  
 JLM  
 est rev D 07.03.20 revF dwg ec

## Additional Product

Job Number:



Seq. #: Machine Or Operation: Description:

1.0 D6014090 ALUMINUM EXTRUSION



Comment: Qty.: 1:0000 f(s)/Unit Total: 1.0000 f(s)

ALUMINUM EXTRUSION

Pick:

Qty	Part Number	Description	Batch
1	D6014-090	Extrusion	B26546

Identify as D3391-3

JF 07/04/22

2.0 MORI SEIKI MORI SEIKI CNC LATHE LARGE



Comment: MORI SEIKI CNC LATHE LARGE

Turn as per Folio FA599

Rev: F &amp; Dwg D3391 Rev: J

JF 07/04/22

3.0 QC2 INSPECT PARTS AS THEY COME OFF MACHINE



Comment: INSPECT PARTS AS THEY COME OFF MACHINE

JF 07.06.04

①

4.0 HAAS1 HAAS CNC VERTICAL MACHINING #1



Comment: HAAS

1-Machine as per Folio FA 599 Rev: AA &amp; Dwg D3391 Rev: F

2-Deburr

JF 07.06.04

①

W/O:		WORK ORDER CHANGES					
DATE	STEP	PROCEDURE CHANGE	By	Date	Qty	Approval Chief Eng / Prod Mgr	Approval QC Inspector

Part No: \_\_\_\_\_ PAR #: \_\_\_\_\_ Fault Category: \_\_\_\_\_ NCR: Yes No DQA: \_\_\_\_\_ Date: \_\_\_\_\_

QA: N/C Closed: \_\_\_\_\_ Date: \_\_\_\_\_

NCR:		WORK ORDER NON-CONFORMANCE (NCR)						
DATE	STEP	Description of NC Section A	Corrective Action Section B			Verification Section C	Approval Chief Eng	Approval QC Inspector
			Initial Chief Eng	Action Description Chief Eng	Sign & Date			

NOTE: Date & initial all entries

Date:

Thursday, 4/11/2007 11:12:50 AM

John Johnston

## Process Sheet

Customer: CU-DAR001 Dart Helicopters Services

Drawing Name: AFT TUBE ASSEMBLY

Job Number: 31859

Part Number: D3391025

Job Number:



Seq. #:

Machine Or Operation:

Description:

5.0

QC2

INSPECT PARTS AS THEY COME OFF MACHINE



Comment: INSPECT PARTS AS THEY COME OFF MACHINE

EG 07-06-09

①

6.0

QC8

SECOND CHECK



Comment: SECOND CHECK

mg 07/06/10

②

7.0

LANDING GEAR 1

LANDING GEAR RESOURCE 1



Comment: LANDING GEAR RESOURCE 1

1-Drill (PILOT HOLE) aft cap holes per Dwg D3391 using DT8803

DP 7-6-13

8.0

BENDING

BENDING MACHINE



Comment: NC Bender

Form as per Dwg D3391 Using Bend Prog 3391025

EL 7-6-14

9.0

QC5

INSPECT WORK TO CURRENT STEP



Comment: INSPECT WORK TO CURRENT STEP

BE 7-6-14

10.0

LANDING GEAR 1

LANDING GEAR RESOURCE 1



Comment: LANDING GEAR RESOURCE 1

1-Open Aft cap pilot hole to .208" as per Dwg D3391

2-Drill float bag holes using DT8809 as per Dwg D3391(Holes marked "A" Only.

3-Drill wearplate holes as per Dwg D3391 using DT8878(Mid Tube) & DT8217 Wearplate Jig.

\*\*\*\*\*Do Not Open To Finished Size\*\*\*\*\*

4-Drill Wearshoe holes as per DWG D3391 using DT8939 locating from 2 previously drilled aft wearplate holes.

5-Open up all wearshoe & wearplate and float bag holes to .257" + countersink as per Dwg D3391.

6-Deburr

DP 7-6-25

DP 7-6-26

Tools: mill

W/O:		WORK ORDER CHANGES						
DATE	STEP	PROCEDURE CHANGE	By	Date	Qty	Approval Chief Eng / Prod Mgr	Approval QC Inspector	

Part No: \_\_\_\_\_ PAR #: \_\_\_\_\_ Fault Category: \_\_\_\_\_ NCR: Yes No DQA: \_\_\_\_\_ Date: \_\_\_\_\_

QA: N/C Closed: \_\_\_\_\_ Date: \_\_\_\_\_

NCR:		WORK ORDER NON-CONFORMANCE (NCR)						
DATE	STEP	Description of NC Section A	Corrective Action Section B			Verification Section C	Approval Chief Eng	Approval QC Inspector
			Initial Chief Eng	Action Description Chief Eng	Sign & Date			

NOTE: Date & initial all entries

Date: Thursday, 19/07/2007 9:04:04 AM  
 User: Linda Lacelle

## Process Sheet

Customer : CU-DAR001 Dart Helicopters Services

Drawing Name : AFT TUBE ASSEMBLY

Job Number : 31859

Estimate Number : 10699

P.O. Number :

This Issue : 19/07/2007 S.O. No. :

Prsht Rev. : NC

First Issue : 17/04/2007 Type : LANDING GEAR

Previous Run : 31858

Part Number : D3391025

Drawing Number : D3391 REV F

Project Number : N/A

Drawing Revision : F

Material :

Due Date : 30/05/2007

Qty: 1 Um: Each

Written By :

Checked &amp; Approved By :

Comment : Est Rev B 06-02-07 ECN773 dwg rev. D EC

Est Rev: C 06-03-28 Update Manufacturing Instructions JLM

est rev D 07.03.20 revF dwg ec

## Additional Product

Job Number:



Seq. #: Machine Or Operation:

Description :

11.0

QC5

INSPECT WORK TO CURRENT STEP



Comment: INSPECT WORK TO CURRENT STEP

En 07/06/20

12.0

HAND FINISHING1

HAND FINISHING RESOURCE #1



Comment: HAND FINISHING RESOURCE #1

Acid etch and Alodine as per QSI 005 4.1

M-p

07/07/19

13.0

POWDER COATING

POWDER COATING



Comment: POWDER COATING

Powder Coat White Gloss (Ref: 4.3.5.1) as per QSI 005 4.3

M 104144

BR/M/07-07-19

14.0

QC3

INSPECT POWDER COAT/CHEMICAL CONVERSION



Comment: INSPECT POWDER COAT/CHEMICAL CONVERSION

FD

07/07/23

15.0

D2646

Aft Cap



Comment: Qty.: 1.0000 Each(s)/Unit Total: 1.0000 Each(s)

Aft Cap

Pick:

Qty Part Number Description Batch

1 D2646 Aft Cap

031335 07-07-23

Date: Thursday, 19/07/2007 9:04:05 AM  
User: Linda Lacelle

## Process Sheet

Customer: CU-DAR001 Dart Helicopters Services

Drawing Name: AFT TUBE ASSEMBLY

Job Number: 31859

Part Number: D3391025

Job Number:



Seq. #: Machine Or Operation: Description :

16.0 D35371 WEARPAD



Comment: Qty.: 1.0000 Each(s)/Unit Total: 1.0000 Each(s)  
WEARPAD

B322274

JS

17.0 D35377 Wearpad



Comment: Qty.: 1.0000 Each(s)/Unit Total: 1.0000 Each(s)  
Wearpad

B31911

18.0 D35531 Gasket



Comment: Qty.: 1.0000 Each(s)/Unit Total: 1.0000 Each(s)  
Gasket

B32740

JS

19.0 D35533 Gasket



Comment: Qty.: 1.0000 Each(s)/Unit Total: 1.0000 Each(s)  
Gasket

B32745

JS

20.0 AEES10KB366 INSERT



Comment: Qty.: 14.0000 Each(s)/Unit Total: 14.0000 Each(s)  
Insert

Pick:

Qty	Part Number	Description	Batch
14	AEES10KB366	Insert	

M104192

JS

21.0 AEES10KB316 INSERT



Comment: Qty.: 2.0000 Each(s)/Unit Total: 2.0000 Each(s)  
INSERT

Pick:

Qty	Part Number	Description	Batch
2	AEES10KB316	Insert	
	or NAS1330C3KB316		

M17905

JS 07-07-24

Date: Thursday, 19/07/2007 9:04:05 AM  
User: Linda Lacelle

## Process Sheet

Customer: CU-DAR001 Dart Helicopters Services

Drawing Name: AFT TUBE ASSEMBLY

Job Number: 31859

Part Number: D3391025

Job Number:



Seq. #:

Machine Or Operation:

Description :

22.0

AESS10KB266

INSERT



Comment: Qty.: 6.0000 Each(s)/Unit Total : 6.0000 Each(s)

INSERT

Pick:

Qty

Part Number

Description

Batch

2

AESS10KB266

Insert

M17905

or NAS1330C3KB266

41

23.0

NAS1330C3KB166

INSERT



Comment: Qty.: 12.0000 Each(s)/Unit Total : 12.0000 Each(s)

INSERT

Pick:

Qty

Part Number

Description

Batch

8

NAS1330C3KB166

Insert

M102848

41

24.0

AN3C4A

BOLT



Comment: Qty.: 6.0000 Each(s)/Unit Total : 6.0000 Each(s)

Bolt

Pick:

Qty

Part Number

Description

Batch

2

AN3C4A

Bolt

M104955

41

25.0

AN3C5A

Bolt



Comment: Qty.: 4.0000 Each(s)/Unit Total : 4.0000 Each(s)

Bolt

M104118

41

26.0

AN960C10L

washer



Comment: Qty.: 10.0000 Each(s)/Unit Total : 10.0000 Each(s)

Inventory

Pick:

Qty

Part Number

Description

Batch

2

AN960C10L

Washer

M105057

41 07-07-24 0

Date: Thursday, 19/07/2007 9:04:05 AM  
User: Linda Lacelle

## Process Sheet

Customer: CU-DAR001 Dart Helicopters Services

Drawing Name: AFT TUBE ASSEMBLY

Job Number: 31859

Part Number: D3391025

Job Number:



Seq. #:

Machine Or Operation:

Description :

27.0

NAS1515H3L

WASHER



Comment: Qty.: 2.0000 Each(s)/Unit Total: 2.0000 Each(s)  
WASHER

Pick:

Qty	Part Number	Description	Batch
2	NAS1515H3L	Washer	M104603

U1

28.0

HAND FINISHING1

HAND FINISHING RESOURCE #1



Comment: SMALL & MEDIUM FAB RESOURCE 1  
1-Install inserts as per Dwg D3391

2-Install Aft Cap as per Dwg D3391

A/ R Sikaflex-241/-291 M104732

Sikaflex expiry date: 07-10

07.07-24(1)

29.0

QC5

INSPECT WORK TO CURRENT STEP



Comment: INSPECT WORK TO CURRENT STEP

En 07/07/24(1)

30.0

PACKAGING 1

PACKAGING RESOURCE #1



Comment: PACKAGING RESOURCE #1

Identify and Stock

Location: PPP 33556

07/08/2001

31.0

QC21

FINAL INSPECTION/W/O RELEASE



Comment: FINAL INSPECTION/W/O RELEASE

07.08.02

Job Completion



07.02.01



<b>DART AEROSPACE LTD</b>		<b>Work Order:</b> 31859
<b>Description:</b> Float Skidtube (412)		<b>Part Number:</b> D3391-3
<b>Inspection Dwg:</b> D3391	<b>Rev:</b> <del>E</del> F PH 07.04.17	Page 1 of 1


### FIRST ARTICLE INSPECTION CHECKLIST

☒ First Article ☐ Prototype

Drawing Dimension	Tolerance	Actual Dimension	Accept	Reject	Method of Inspection	Comments
14.000	+/-0.010	14.000	✓			
3.500	+/-0.010	3.505	✓			
88.93	+/-0.030	88.93	✓			
44.995	+/-0.030	44.995	✓			
3.200	+/-0.010	3.200	✓			
1.526	+0.000/-0.030	1.524	✓			
0.200	+/-0.010	.198	✓			
7.500	+/-0.010	7.500	✓			
27.750	+/-0.010	27.750	✓			
31.750	+/-0.010	31.750	✓			
35.250	+/-0.010	35.250	✓			
<del>0.400</del>	<del>+/-0.010</del>					OR. d7
<del>Ø0.208</del>	<del>+0.005/-0.004</del>					
3.300	+/-0.010	3.298	✓			
0.200	+/-0.010	.200	✓			
3.520	+/-0.010	3.522	✓			
0.687	+0.010/-0.000	.689	✓			
R0.062	+/-0.010	.062	✓			
Ø0.484	+0.005/-0.001	.486	✓			

<b>Measured by:</b> SP	<b>Audited by:</b> GML	<b>Prototype Approval:</b>	N/A
<b>Date:</b> 07/04/22	<b>Date:</b> 07/06/10	<b>Date:</b>	N/A

Rev	Date	Change	Revised by	Approved
A	06.04.24	New Issue P/O D3391-025	KJ/JLM	
B	06.06.19	Dwg revision update	KJ/JLM	



**RELEASED**  
07.03.13 AH  
per ECH #934

#### D3391-041/-043 FLOAT SKIDTUBE ASSEMBLY PARTS LIST

QTY -041	QTY -043	PART NUMBER	DESCRIPTION
X	X	D3391-041	FLOAT SKIDTUBE ASSEMBLY
		D3391-043	FLOAT SKIDTUBE ASSEMBLY
1		D3391-011	FWD TUBE ASSEMBLY
1		D3391-013	MID TUBE ASSEMBLY
1		D3391-015	AFT TUBE ASSEMBLY
1		D3391-021	FWD TUBE ASSEMBLY
1		D3391-023	MID TUBE ASSEMBLY
1		D3391-025	AFT TUBE ASSEMBLY
1	1	D3564-1	WEARSHOE
1	1	D3564-3	WEARSHOE
1	1	D3564-5	WEARSHOE
2	2	D3566-1	GASKET
1	1	D3566-5	GASKET
24	24	AN3C4A	BOLT
12	12	AN3C6A	BOLT
8	8	AN3C7A	BOLT
44	44	AN960C10L	WASHER
4	4	MS27039C4-12	SCREW
4	4	NAS1515H4L	WASHER
4	4	AN960C416L	WASHER

#### GENERAL NOTES

- ALL DIMENSIONS ARE IN INCHES
- TOLERANCES ARE PER DART QSI 018 UNLESS OTHERWISE NOTED
- FINISH: ACID ETCH AND ALODINE PER DART QSI 005 4.1  
POWDER COAT WHITE (4.3.5.1) PER DART QSI 005 4.3
- SPRAY INSIDE OF TUBE WITH A COAT OF LPS LABORATORIES "LPS-3" AFTER FINISH AND AFTER INSTALLATION OF INSERTS. COAT ALL EXPOSED FASTENERS WITH LPS LABORATORIES "LPS PROCYON" AFTER FINAL ASSEMBLY, CLEAN EXCESS OFF POWDER COATING WITH MEK DEGREASER.
- USE DART DRILL TEMPLATE DT8217 TO LOCATE AND DRILL 'E' SIZE HOLES (Ø0.250-Ø0.257) FOR WEARSHOE INSERTS. C'SINK Ø0.391/Ø0.425 x 100" AS APPLICABLE AND INSTALL INSERTS EXCEPT WHERE INDICATED.


COPYRIGHT © 2006 BY DART AEROSPACE USA, INC.

THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL  
AND IS SUPPLIED ON THE EXPRESS CONDITION  
THAT IT IS NOT TO BE USED FOR ANY PURPOSE  
OR COPIED OR COMMUNICATED TO ANY OTHER  
PERSON WITHOUT WRITTEN PERMISSION FROM  
DART AEROSPACE USA, INC.


F	07.01.18	ADD SS WEARSHOE, GASKET REMOVE FWD SADDLE HOLE -011/-021
E	06.04.25	CHANGE TOLERANCE, EASE MANUFACTURE
D	06.01.23	UPDATE TOLERANCE, CHANGE HOLE SIZE
C	05.09.27	LENGTHEN AFT EXTENSION
B	05.06.10	DRAWING UPDATES
A	05.02.07	NEW ISSUE
DESIGN	PH	DRAWN BY PH
CHECKED	#	APPROVED #
DATE	07.01.18	DRAWING NO. D3391
		TITLE 412 FLOAT SKIDTUBE
		REV. F SHEET 1 OF 5 SCALE NTS

070318579


**RELEASED**  
 17.03.13 AH  
 per ECN #934




**D3391-011 ASSEMBLY AND BENDING DETAIL**




**DETAIL A**  
 (SCALE 1:5)




**SECTION E-E**  
 (SCALE 1:5)



**SECTION D-D**  
 (SCALE 1:5)




**SECTION C-C**  
 (SCALE 1:5)



**VIEW Z-Z**  
 (SCALE 1:5)


**D3391-011/-021 WEARSHOE ASSEMBLY**




**D3391-011/-021 FWD TUBE ASSEMBLY PARTS LIST**

QTY - 011	QTY - 021	PART NUMBER	DESCRIPTION
X		D3391-011	FWD TUBE ASSEMBLY
	X	D3391-021	FWD TUBE ASSEMBLY
1	1	D6013-047	FWD TUBE
1	1	D3401-041	TOW CAP
1	1	D3564-13	WEARSHOE
1	1	D3566-13	GASKET
10	10	AN3C4A	BOLT
4	4	NAS1515H3L	WASHER
10	10	AN960C10L	WASHER
30	20	NAS1330S3KB166	INSERT (OR NAS1330C3KB166)

5  
 DRILL "E"  
 (0.250-0.257)  
 C'SINK (0.391 X 100")  
 INSTALL  
 NAS1330S3KB166  
 (12 PLACES)





**SECTION B-B**  
 (SCALE 1:5)




**D3391-1 DRILLING AND CUTTING DETAIL**  
 (MAKE FROM D6013-047 SKIDTUBE MATERIAL)




COPYRIGHT © 2005 BY DART AEROSPACE USA, INC.		DESIGN PH	DRAWN BY PH	<b>DART</b> DART AEROSPACE USA, INC. PORT HADLOCK, MA
CHECKED [Signature]	APPROVED [Signature]	DRAWING NO. D3391		REV. F SHEET 2 OF 5
DATE 07.01.18		TITLE 412 FLOAT SKIDTUBE		SCALE 1:10






**RELEASED**  
07.03.13 RH  
Per ELM #934



DRILL 'Q' (0.332-0.338)  
INSTALL NAS1329S4KB140 INSERT  
MS27039C4-08 SCREW  
NAS1515H4L WASHER  
AN960C416L WASHER  
(TYP 4 PLACES)



DRILL 'E' (0.250-0.257)  
C'SINK (0.391X100)  
INSTALL NAS1330S3KB116 INSERT  
MS27039C1-09 SCREW  
NAS1515H3L WASHER  
AN960C10L WASHER  
(TYP 4 PLACES)




# **D3391-013/-023 MID TUBE ASSEMBLY PARTS LIST**

QTY - 013	QTY - 023	PART NUMBER	DESCRIPTION
X		D3391-013	MID TUBE ASSEMBLY
	X	D3391-023	MID TUBE ASSEMBLY
1	1	D2500-1-100	EXTRUSION
1	1	D3389-1	WEB
24	20	NAS1330S3KB116	INSERT (OR NAS1330C3KB116)
24	10	NAS1330S3KB166	INSERT (OR NAS1330C3KB166)
4		NAS1329S4KB140	INSERT (OR NAS1329C3KB140)
4		NAS1515H3L	WASHER
4		AN960C10L	WASHER
4		NAS1515H4L	WASHER
4		AN960C416L	WASHER
4		MS27039C1-09	SCREW
4		MS27039C4-08	SCREW

## **D3391-013/-023 MID TUBE ASSEMBLY**

- MATERIAL: MAKE FROM D2500-1-100 EXTRUSION
- INSTALL D3389-1 WEB TO OUTER TUBE USING SIKAFLEX-241/-291 PER QSI 015



REMOVE 0.225  
FROM TOP AND BOTTOM  
TO 3.800  
(0.7 FROM BOTH ENDS)


**SECTION Y-Y**  
(SCALE 1:4)

**SECTION G-G**  
(SCALE 1:4)


**SECTION H-H**  
(SCALE 1:4)

COPYRIGHT © 2005 BY DART AEROSPACE USA, INC.  
THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL  
AND IS SUPPLIED ON THE EXPRESS CONDITION  
THAT IT IS NOT TO BE USED FOR ANY PURPOSE  
OR COPIED OR COMMUNICATED TO ANY OTHER  
PERSON WITHOUT WRITTEN PERMISSION FROM  
DART AEROSPACE USA, INC.


DESIGN RH	DRAWN BY RH	<b>DART</b> DART AEROSPACE USA, INC. PORT HADLOCK, MA	REV. F
CHECKED #	APPROVED #	DRAWING NO. D3391	SHEET 3 OF 5
DATE 07.01.18	TITLE 412 FLOAT SKIDTUBE	SCALE 1:20	




VIEW BB-BB  
(SCALE 1:3)




D3391-3 AFT DRILLING AND CUTTING DETAIL  
(MAKE FROM D6014-090 SKIDTUBE MATERIAL)




DETAIL V  
(SCALE 1:2)




SECTION AA-AA  
(SCALE 1:2)




SECTION N-N  
(SCALE 1:2)




SECTION P-P  
(SCALE 1:2)




SECTION Q-Q  
(SCALE 1:2)



SECTION R-R  
(SCALE 1:2)



DETAIL S  
(SCALE 1:3)




VIEW W-W  
(SCALE 1:3)


RELEASED  
07 05 13 PM  
P/N ELN #934

COPYRIGHT © 2005 BY DART AEROSPACE USA, INC.  
THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL  
AND IS SUPPLIED ON THE EXPRESS CONDITION  
THAT IT IS NOT TO BE USED FOR ANY PURPOSE  
OR COPIED OR COMMUNICATED TO ANY OTHER  
PERSON WITHOUT WRITTEN PERMISSION FROM  
DART AEROSPACE USA, INC.


DESIGN PH	DRAWN BY PH	<b>DART</b> DART AEROSPACE USA, INC. PORT HADLOCK, MA	
CHECKED #	APPROVED #	DRAWING NO. D3391	REV. F SHEET 4 OF 5
DATE 07.01.18	TITLE 412 FLOAT SKIDTUBE		SCALE 1:12




**D3391-015 BENDING AND ASSEMBLY DETAIL**



**D3391-025 BENDING AND ASSEMBLY DETAIL**




**D3391-015 INSERT AND WEARPAD INSTALLATION DETAIL**  
(SEE TABLE)





**D3391-025 INSERT AND WEARPAD INSTALLATION DETAIL**  
(SEE TABLE)

**D3391-015/-025 AFT TUBE ASSEMBLY PARTS LIST**

QTY - 015	QTY - 025	PART NUMBER	DESCRIPTION
X	X	D3391-015	AFT TUBE ASSEMBLY
		D3391-025	AFT TUBE ASSEMBLY
1	1	D6014-090	AFT TUBE
1	1	D2646	AFT CAP
1	1	D3537-1	WEARPAD
1	1	D3537-7	WEARPAD
1	1	D3553-1	GASKET
1	1	D3553-3	GASKET
18	14	NAS1330S3KB366	INSERT (OR AES10KB366)
4	2	NAS1330S3KB316	INSERT (OR NAS1330C3KB316)
8	6	NAS1330S3KB266	INSERT (OR NAS1330C3KB266)
4		NAS1330S3KB216	INSERT (OR NAS1330C3KB216)
16	12	NAS1330S3KB166	INSERT (OR NAS1330C3KB166)
4		NAS1330S4KB151	INSERT (OR NAS1330C4KB151)
6	6	AN3C4A	BOLT
4	4	AN3C5A	BOLT
2	2	NAS1515H3L	WASHER
10	10	AN960C10L	WASHER



DRILL 'Q' (#0.332-#0.336)  
C'SINK (#0.529X100)  
NAS1330S4KB151 INSERT (1)  
(4 PLACES)



C'SINK AND INSTALL NAS1330S3KBXXX IN HOLES MARKED CS1-CS6 AS FOLLOWS

HOLES MARKED	QTY D3391-015	QTY D3391-025	C'SINK	P/N
CS1	18	14	Ø0.425	NAS1330S3KB366
CS2	4		Ø0.391	NAS1330S3KB366
CS3	4	2	Ø0.391	NAS1330S3KB316
CS4	8	6	Ø0.391	NAS1330S3KB266
CS5	4		Ø0.391	NAS1330S3KB216
CS6	16	12	Ø0.391	NAS1330S3KB166

COPYRIGHT © 2005 BY DART AEROSPACE USA, INC.

THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COPIED OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE USA, INC.

DESIGN	DRAWN BY	<b>DART</b> DART AEROSPACE USA, INC.	REV. F
CHECKED	APPROVED	DRAWING NO. D3391	SHEET 5 OF 5
DATE	TITLE	SCALE	
07.01.18	412 FLOAT SKIDTUBE	1:12	

**RELEASED**  
07.03.13 RH  
per ECN #734